

FORM PTO-1390 (Modified)
(REV 10-95)

U.S. DEPARTMENT OF COMMERCE PATENT AND TRADEMARK OFFICE

ATTORNEY'S DOCKET NUMBER

TRANSMITTAL LETTER TO THE UNITED STATES
DESIGNATED/ELECTED OFFICE (DO/EO/US)
CONCERNING A FILING UNDER 35 U.S.C. 371

9847-0006-6X PCT

U.S. APPLICATION NO. (IF KNOWN, SEE 37 CFR

09/147318

INTERNATIONAL APPLICATION NO

PCT/SE97/00906

INTERNATIONAL FILING DATE

27 May 1997

PRIORITY DATE CLAIMED

29 May 1996 earliest

TITLE OF INVENTION

ROTATING ELECTRICAL MACHINE COMPRISING HIGH-VOLTAGE STATOR WINDING AND
SPRING-DEVICE SUPPORTING THE WINDING AND METHOD FOR MANUFACTURING SUCH MACHINE

APPLICANT(S) FOR DO/EO/US

Mats LEIJON, et al

Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:

1. ☒ This is a **FIRST** submission of items concerning a filing under 35 U.S.C. 371.
2. ☐ This is a **SECOND** or **SUBSEQUENT** submission of items concerning a filing under 35 U.S.C. 371.
3. ☒ This is an express request to begin national examination procedures (35 U.S.C. 371(f)) at any time rather than delay examination until the expiration of the applicable time limit set in 35 U.S.C. 371(b) and PCT Articles 22 and 39(1).
4. ☒ A proper Demand for International Preliminary Examination was made by the 19th month from the earliest claimed priority date.
5. ☒ A copy of the International Application as filed (35 U.S.C. 371 (c) (2))
 - a. ☐ is transmitted herewith (required only if not transmitted by the International Bureau).
 - b. ☒ has been transmitted by the International Bureau.
 - c. ☐ is not required, as the application was filed in the United States Receiving Office (RO/US).
6. ☐ A translation of the International Application into English (35 U.S.C. 371(c)(2)).
7. ☒ A copy of the International Search Report (PCT/ISA/210).
8. ☒ Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371 (c)(3))
 - a. ☐ are transmitted herewith (required only if not transmitted by the International Bureau).
 - b. ☐ have been transmitted by the International Bureau.
 - c. ☐ have not been made, however, the time limit for making such amendments has NOT expired.
 - d. ☒ have not been made and will not be made
9. ☐ A translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371(c)(3)).
10. ☐ An oath or declaration of the inventor(s) (35 U.S.C. 371 (c)(4)).
11. ☒ A copy of the International Preliminary Examination Report (PCT/IPEA/409).
12. ☐ A translation of the annexes to the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371 (c)(5)).

Items 13 to 18 below concern document(s) or information included:

13. ☐ An Information Disclosure Statement under 37 CFR 1.97 and 1.98.
14. ☐ An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.28 and 3.31 is included.
15. ☒ A **FIRST** preliminary amendment.
A **SECOND** or **SUBSEQUENT** preliminary amendment.
16. ☐ A substitute specification
17. ☐ A change of power of attorney and/or address letter.
18. ☐ Certificate of Mailing by Express Mail
19. ☒ Other items or information:

Notice of Priority

Clean Copy of Specification (as amended by Preliminary Amendment)

PCT/IB/304

Letter Requesting Approval of Drawing Changes

Request For Consideration of Documents Cited in International Search Report

ATION NO. (IF KNOWN, SEE 37 CFR

INTERNATIONAL APPLICATION NO.

ATTORNEY'S DOCKET NUMBER

PCT/SE97/00906

9847-0006-6X PCT

The following fees are submitted:

NATIONAL FEE (37 CFR 1.492 (a) (1) - (5)) :

- Search Report has been prepared by the EPO or JPO \$930.00
- ☐ International preliminary examination fee paid to USPTO (37 CFR 1.482) \$670.00
- ☐ No international preliminary examination fee paid to USPTO (37 CFR 1.482) but international search fee paid to USPTO (37 CFR 1.445(a)(2)) \$760.00
- ☒ Neither international preliminary examination fee (37 CFR 1.482) nor international search fee (37 CFR 1.445(a)(2)) paid to USPTO \$970.00
- ☐ International preliminary examination fee paid to USPTO (37 CFR 1.482) and all claims satisfied provisions of PCT Article 33(2)-(4) \$96.00

CALCULATIONS PTO USE ONLY

ENTER APPROPRIATE BASIC FEE AMOUNT =

\$970.00

Surcharge of \$130.00 for furnishing the oath or declaration later than months from the earliest claimed priority date (37 CFR 1.492 (e)). ☐ 20 ☒ 30

\$130.00

CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE	
Total claims	19 - 20 =	0	x \$18.00	\$0.00
Independent claims	3 - 3 =	0	x \$78.00	\$0.00
Multiple Dependent Claims (check if applicable)			<input type="checkbox"/>	\$0.00

TOTAL OF ABOVE CALCULATIONS = \$1,100.00

Reduction of 1/2 for filing by small entity, if applicable. Verified Small Entity Statement must also be filed (Note 37 CFR 1.9, 1.27, 1.28) (check if applicable). ☐ \$0.00

SUBTOTAL = \$1,100.00

Processing fee of \$130.00 for furnishing the English translation later than months from the earliest claimed priority date (37 CFR 1.492 (f)). ☐ 20 ☐ 30 + \$0.00

TOTAL NATIONAL FEE = \$1,100.00

Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) (check if applicable). ☐ \$0.00

TOTAL FEES ENCLOSED = \$1,100.00

Amount to be: refunded \$ charged \$

- ☒ A check in the amount of \$1,100.00 to cover the above fees is enclosed.
- ☐ Please charge my Deposit Account No. in the amount of to cover the above fees. A duplicate copy of this sheet is enclosed.
- ☒ The Commissioner is hereby authorized to charge any fees which may be required, or credit any overpayment to Deposit Account No. 15-0030 A duplicate copy of this sheet is enclosed.

NOTE: Where an appropriate time limit under 37 CFR 1.494 or 1.495 has not been met, a petition to revive (37 CFR 1.137(a) or (b)) must be filed and granted to restore the application to pending status.

SEND ALL CORRESPONDENCE TO:

OBLON, SPIVAK, McCLELLAND, MAIER & NEUSTADT, P.C.
Crystal Square Five, Fourth Floor
1755 Jefferson Davis Highway
Arlington, Virginia 22202
US

Telephone Number (703) 413-3000
Facsimile Number (703) 413-2220

SIGNATURE

Gregory J. Maier

NAME

25,599

REGISTRATION NUMBER

DATE

Nov 25, 1998

09/147318

300 Rec'd PCT/PTO 27 NOV 1998

9847-0006-6X PCT

IN THE UNITED STATES PATENT & TRADEMARK OFFICE

IN RE APPLICATION OF: :

MATS LEIJON ET AL : ATTN: APPLICATION DIVISION

SERIAL NO: NEW PCT APPLICATION :
(BASED ON PCY/SE97/00906)

FILED: HEREWITH :

FOR: ROTATING ELECTRICAL MACHINE
COMPRISING HIGH-VOLTAGE STATOR
WINDING AND SPRING-DEVICE
SUPPORTING THE WINDING AND
METHOD FOR MANUFACTURING
SUCH MACHINE

PRELIMINARY AMENDMENT

ASSISTANT COMMISSIONER FOR PATENTS
WASHINGTON, D.C. 20231

SIR:

Prior to examination on the merits, please amend the above-identified application as follows:

IN THE SPECIFICATION

Page 1, line 1, delete in its entirety and insert therefor

--9847-0006-6X PCT

TITLE OF THE INVENTION--;

lines 1-3, delete in their entirety and insert therefor

--ROTATING ELECTRICAL MACHINE WITH HIGH-VOLTAGE
STATOR WINDING AND SPRING-DEVICE SUPPORTING
THE WINDING AND METHOD FOR MANUFACTURING THE SAME

BACKGROUND OF THE INVENTION

Field of the Invention--;

line 4, delete "of the";

line 5, delete "type described in the preamble to claim 1;

lines 9-10, make as one paragraph;

lines 10-11, change "of the type described in the preamble to claim 13" to --for
making the machine--;

between prenumbered lines 17 and 18, insert

--Discussion of the Background--;

line 19, after "range" insert --of--;

line 27, after "cables" insert --, cross-linked polyethylene--;

line 29, delete "XPLE=Cross-linked polyethylene".

Page 2, line 3, change "vibration" to --vibrate--;

line 13, delete in its entirety and insert therefor --generator is described in U.S.

Patent No. 4,429,244; No. 4,164,672; and No. 3,743,867--;

line 20, after "This" insert --article--; same line, after "Parson" insert --in--;

and

line 30, change "US" to --U.S. Patent No.--.

Page 3, line 3, after "having" insert --an--;

line 5, change "means" to --way--;

line 13, change "comprising" to --having--; same line, change "plate" to
--plates--;

line 20, change "means" to --way--;
line 22, change "consists of" to --has--;
line 31, change "consists of" to --uses--;
line 35, change "place" to --space--.

Page 4, line 20, after "with" insert --a--;

line 26, change "an" to --a--;
line 27, change "obvious" to --clear--; and
between lines 31 and 32, insert

--SUMMARY OF THE INVENTION--.

Page 5, line 8, change "mains" to --main--;

line 18, change "the" (first occurrence) to --an--;
line 23, change "consists of" to --has--;
lines 27-28, delete in their entirety and insert therefor --described herein--;
lines 30 and 32, change "application" to --document--;
line 31, change "have" to --refer to--; same line, after "as" insert --a--;
lines 33 and 35, change "implied" to --meant--.

Page 6, line 3, change "as defined in claim 1" to --occurs--;

line 6, after "inserted," insert --and--;
line 10, change "damages" to --damage--;
line 12, change "lead-through" to --lead-throughs--;
line 14, after "method" insert --,--;
line 15, change "lead through" to --lead-through--;
line 20, change "direction" to --directions--;

lines 26-27, change "lead-trhough" to --lead-through--.

Page 7, line 10, after "in" insert --an--;

line 11, change "lead-theough" to --lead-through--;

lines 13-14, delete in their entirety;

line 19, change "as discussed in the introduction" to --as previously discussed--;

line 23, delete in its entirety;

line 24, delete "in the sub-claims to claim 13.";

between lines 26 and 28, insert

~~--BRIEF DESCRIPTION OF THE DRAWINGS--~~;

line 29, change "," to --:--;

line 31, change "the" to --a--;

lines 32 and 35, change "," to --:-- and

line 34, change "cross- section" to --cross-section--.

Page 8, lines 2, 5, 8 and 11, change "invention," to --invention;--;

line 13, change "deactivated," to --deactivated; and--;

between lines 16 and 18, insert

~~--DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS~~

Referring now to the drawings, wherein like reference numerals designate identical or corresponding parts throughout the several views, and more particularly to Figure 1,--;

line 18, change "In" to --in--;

line 19, change "its" to --a--; same line, change "stator is composed in" to --stator 1 itself is composed in a--;

line 20, change "The figure" to --Figure 1--;

line 27, change "comprises" to --has--;

line 29, after "The" insert --outer--;

line 36, after "these" insert --wide parts 7--.

Page 9, line 1, change "lead-throught" to --lead-through--;

line 2, after "in" insert --the inward--; same line, delete "inwards";

line 7, change "9. 19" to --9, 10--;

line 10, change "comprises" to --includes--;

line 15, after "concept" insert --of--;

line 23, change "arc" to --are--.

Page 10, line 2, after "in" insert --the--;

line 5, after "cylinder" insert --and--;

line 8, change "means" to --way--;

line 9, change "lead-troughs" to --lead-throughs--; same line, change "lead-throughs" to --lead-through--;

line 31, change "13" to --13b--.

Page 11, line 18, change "and then" to --when--;

line 29, change "Figure" to --figure--;

line 31, after "lid 17 in" insert --a--; and

line 34, change "means" to --way--.

IN THE CLAIMS

Please cancel without prejudice or disclaimer Claims 1-17.

Please add new Claims 18-36 as follows:

–18. A method for manufacturing a stator with a stator winding for a rotating electric machine, comprising the steps of:

drawing a high-voltage cable having an outer semi-conducting layer through a first slot and a second slot in the stator so as to form a part of the stator winding, including

inserting said high-voltage cable through at least one of said first slot and said second slot while a spring member therein being deactivated, said at least one of said first slot and said second slot being a supporting slot; and

activating said spring member after said inserting step.

19. A method according to claim 18, further comprising the steps of:

supporting the spring member with a slot wall of said supporting slot;

positioning a support body between the spring member and at least one cable lead-through; and

pressing the support body against said at least one cable lead-through.

20. A method according to claim 19, further comprising the steps of:

arranging another spring member on another slot wall of said supporting slot, said another slot wall being opposite to said slot wall and immediately opposite to said spring member;

positioning another support body between the another spring member and said at least one cable lead-through; and

pressing said second support body against said at least one cable lead-through.

21. A method according to claim 19, further comprising a step of:

arranging a pressure member between said support body and said another slot wall and pressing said pressure member against said spring member via said support body.

22. A method as claimed in claim 20, further comprising a step of:

arranging a pressure member between the support body and another support body and pressing the pressure member by way of said support body and said another support body against the spring member and the another spring member.

23. The method of claim 21, wherein:

said arranging step comprises arranging said pressure member so as to deactivate said spring member and activating said spring member when removing the pressure member.

24. A method according to claim 22, wherein:

said arranging step comprises arranging said pressure member so as to deactivate said spring member and activating said spring member when removing the pressure member.

25. A method as claimed in claim 18, further comprising a step of:

disposing said spring member in said supporting slot, wherein said spring member comprises a corrugated, laminated, plate spring.

26. A method as claimed in claim 25, wherein:

said arranging step, includes deactivating the spring member by gluing the corrugated, laminated, plate spring to a flat surface so as to have the corrugated, laminated, plate spring acquire a flat shape, and said activating step includes releasing a glue joint formed in said gluing step.

27. A method as claimed in claim 26, wherein:

said gluing step includes gluing said corrugated, laminated, plate spring to an inside of a slot lid fitted at a radially inwardly directed opening of the supporting slot.

28. A method as claimed in claim 26, wherein:

said releasing step includes releasing the glue joint by heating the glue joint with heat generated in the high-voltage cable.

29. A method as claimed in claim 27, wherein:

said releasing step includes releasing the glue joint by knocking against an outside of the slot lid.

30. A method as claimed in claim 18, further comprising a step of:

disposing said spring member in said supporting slot, wherein said spring member extends substantially along an entire axial extension of the stator.

31. A rotating electric machine comprising:

a stator having a slot;

a winding having a high-voltage cable being drawn through said slot, wherein said high-voltage cable having

an insulation system with an inner semiconducting layer, an outer semiconducting layer, and a solid insulation disposed between said inner semiconducting layer and said outer semiconducting layer, said inner semiconducting layer and said outer semiconducting layer each constituting an equipotential surface; and

a corrugated, laminated plate spring biased against a cable lead-through of said high-voltage cable so as to press against said cable lead-through.

32. A machine as claimed in claim 31, wherein:

at least one of said inner semiconducting layer and said outer semiconducting layer having a same coefficient of thermal expansion as said solid insulation.

33. A rotating electric machine as claimed in claim 31, wherein:

said corrugated, laminated plate spring being arranged between a slot wall of said slot and a support member which is held by being pressed by the corrugated, laminated plate spring against the cable lead-through.

34. A rotating electric machine as claimed in claim 31, wherein:

said corrugated, laminated plate spring being arranged between a slot lid fitted on an inwardly directed opening of the slot and a radially innermost cable lead-through.

35. A rotating electric machine as claimed in claim 31, wherein:

said corrugated, laminated plate spring having a shape that extends along substantially a whole axial extension of the stator.

36. A rotating electric machine comprising:

a stator having a slot;

a high-voltage winding disposed in said slot, having

means for conducting an electrical current in said high-voltage winding,

means for electrically insulating said means for conducting, said means for electrically insulating having,

means for creating a first equipotential surface around said means for conducting,

means for creating a second equipotential surface around said means for creating the first equipotential surface, and

means for separating said first equipotential surface from said second equipotential surface; and

means for exerting a pressure against said winding in said slot.--

IN THE ABSTRACT OF THE DISCLOSURE

--A rotating electric machine with high-voltage stator winding and spring-device supporting the winding and method for manufacturing the same is employed for high-voltage applications. In particular, the machine includes a stator with a winding that is made of a high-voltage cable that is drawn through a slot in the stator of the rotating electric machine. A spring member biases the high-voltage cable against a wall of the stator so as to avoid damaging an outer surface of the cable during operation of the machine. The outer surface of the cable is susceptible to being damaged because an outer surface of the cable includes a semiconducting material that could possibly be damaged if subject to vibration or abrasion against a slot wall of the slot.--

REMARKS

Favorable consideration of this application as presently amended and in light of the following discussion is respectfully requested.

Claims 18-35 are pending, Claims 1-17 having been canceled without prejudice or disclaimer and Claims 18-36 having been added by way of the present amendment. New Claims 18-36 find support in original Claims 1-17 and in the specification as originally filed, and consequently no new matter is added.

A separate letter requesting approval of a drawing change is filed herewith, correcting a reference number in the Figures.

While numerous amendments have been made to the specification, consistent with accepted U.S. patent application drafting format, each amendment is believed to be made as a matter of form. However, to the extent any amendment is substantively inconsistent with the

originally filed specification, the language included in the originally filed specification should be construed as containing the controlling language. Due to the large number of changes, and for the examiner's convenience, a "clean copy" of the specification is filed herewith that includes all of the amendments made by way of the present preliminary amendment.

Consequently, in view of the present amendment, an action on the merits is earnestly solicited.

Respectfully submitted,

OBLON, SPIVAK, MCCLELLAND,
MAIER & NEUSTADT, P.C.



Gregory J. Maier
Attorney of Record
Registration No. 25,599
Bradley D. Lytle
Registration No. 40,073

Crystal Square Five - Fourth Floor
1755 Jefferson Davis Highway
Arlington, Virginia 22202
(703) 413-3000
Fax: (703) 413-2220
I:\atty\BDL\9847\98470006.PR

09/147318

300 Rec'd PCT/PTO 27 NOV 1998

9847-0006-6X PCT

IN THE UNITED STATES PATENT & TRADEMARK OFFICE

IN RE APPLICATION OF: :

MATS LEIJON ET AL : ATTN: APPLICATION DIVISION

SERIAL NO: NEW PCT APPLICATION :
(BASED ON PCY/SE97/00906)

FILED: HERewith :

FOR: ROTATING ELECTRICAL MACHINE
COMPRISING HIGH-VOLTAGE STATOR
WINDING AND SPRING-DEVICE
SUPPORTING THE WINDING AND
METHOD FOR MANUFACTURING
SUCH MACHINE

LETTER REQUESTING APPROVAL OF DRAWING CHANGES

ASSISTANT COMMISSIONER FOR PATENTS
WASHINGTON, D.C. 20231

SIR:

Please review for approval the proposed changes to the Formal Drawings shown in **RED** on the attached photocopies of the drawings.

Once these changes have been reviewed and approved by the Examiner in charge of this case, instructions for their implementation will be forwarded to an approved bonded draftsman.

Respectfully submitted,


OBLON, SPIVAK, McCLELLAND,
MAIER & NEUSTADT, P.C.

Gregory J. Maier
Registration No: 25,599
William E. Beaumont
Registration No: 30,996
Attorneys of Record


Fourth Floor
1755 Jefferson Davis Highway
Arlington, Virginia 22202
(703) 413-3000
I:\atty\BDL\9847\98470006.DRAW

Bradley D. Lytle
BRADLEY D. LYTLE
REGISTRATION NO. 40,073


5-6-5



4-9-54



5-9-2



28 Rec'd PCT/PTO 27 NOV1998

Rotating electrical machine comprising high-voltage statorwinding and spring-device supporting the winding and method for manufacturing such machine.

- The present invention relates in a first aspect to a rotating electric machine of the
- 5 type described in the preamble to claim 1, e.g. synchronous machines, normal asynchronous machines as well as dual-fed machines, applications in asynchronous static current converter cascades, outerpole machines and synchronous flow machines.
- 10 A second aspect of the invention relates to a method of the type described in the preamble to claim 13.
- The machine is intended primarily as a generator in a power station for generating electric power. The machine is intended to be used at high voltages. High
- 15 voltages shall be understood here to mean electric voltages in excess of 10 kV. A typical operating range for the machine according to the invention may be 36 to 800 kV.
- Similar machines have conventionally been designed for voltages in the range
- 20 6-30 kV, and 30 kV has normally been considered to be an upper limit. This generally means that a generator must be connected to the power network via a transformer which steps up the voltage to the level of the power network, i.e. in the range of approximately 100-400 kV.
- 25 By using high-voltage insulated electric conductors, in the following termed cables, with solid insulation similar to that used in cables for transmitting electric power in the stator winding (e.g. XPLE cables) the voltage of the machine may be increased to such levels that it may be connected directly to the power network without an intermediate transformer. XPLE = Cross-linked polyethylene .
- 30 This concept generally implies that the slots in which the cables are placed in the stator be deeper than conventional technology requires (thicker insulation due to higher voltage and more turns in the winding). This entails new problems with regard to cooling, vibrations and natural frequencies in the region of the coil end,
- 35 teeth and winding.

- Securing the cable in the slot is also a problem - the cable must be inserted into the slot without its outer layer being damaged. The cable is subjected to currents having a frequency of 100 Hz which cause a tendency to vibration and, besides
- 5 manufacturing tolerances with regard to the outer diameter, its dimensions will also vary according to variations in temperature (i.e. load variations).

- Although the predominant technology when supplying current to a high-voltage network for transmission, sub-transmission and distribution, involves inserting a
- 10 transformer between the generator and the power network as mentioned in the introduction, it is already known that attempts are being made to eliminate the transformer by generating the voltage directly at the level of the network. Such a generator is described in US-4 429 244, US-4 164 672 and US-3 743 867.

- 15 The manufacture of coils for rotating machines is considered possible with good results up to a voltage range of 10-20 kV.

- Attempts at developing a generator for voltages higher than this have been in progress for some time, as is evident from "Electrical World", October 15 1932,
- 20 pages 524-525, for instance. This describes how a generator designed by Parson 1929 was constructed for 33 kV. A generator in Langerbrugge, Belgium, is also described which produced a voltage of 36 kV. Although the article also speculates on the possibility of increasing the voltage levels, development of the concepts upon which these generators were based ceased. This was primarily due to
- 25 deficiencies in the insulating system where several layers of varnish-impregnated mica foil and paper were used.

- Certain attempts at lateral thinking in the design of synchronous generators are described in an article entitled "Water-and-oil-cooled Turbogenerator TVM-300"
- 30 in J. Elektrotechnika, No. 1 1970, pages 6-8 of US 4,429,244 "Stator of generator" and in Russian patent specification CCCP Patent 955369.

- The water-and-oil-cooled synchronous machine described in J. Elektrotechnika is intended for voltages up to 20 kV. The article describes a new insulation system
- 35 consisting of oil/paper insulation which enabled the stator to be completely immersed in oil. The oil can then be used as coolant at the same time as

constituting insulation. A dielectric oil-separating ring is provided at the internal surface of the core to prevent oil in the stator from leaking out towards the rotor. The stator winding is manufactured from conductors having oval, hollow shape, provided with oil and paper insulation. The coil sides with the insulation are retained in the slots with rectangular cross- section by means of wedges. Oil is used as coolant both in the hollow conductors and in cavities in the stator walls. However, such cooling systems necessitate a large number of connections for both oil and electricity at the coil ends. The thick insulation also results in increased radius of curvature of the conductors which in turn causes increased size of the coil overhang.

The above-mentioned US patent relates to the stator part of a synchronous machine comprising a magnetic core of laminated plate with trapezoid slots for the stator winding. The slots are stepped since the need for insulation of the stator winding is less in towards the rotor where the part of the winding located closest to the neutral point is situated. The stator part also includes dielectric oil-separating cylinders nearest the inner surface of the core. This part will increase the excitation requirement in comparison with a machine lacking this ring. The stator winding is manufactured from oil-saturated cables having the same diameter for each layer of the coil. The layers are separated from each other by means of spacers in the slots and secured with wedges. Characteristic of the winding is that it consists of two "half-windings" connected in series. One of the two half-windings is situated centrally inside an insulating sheath. The conductors of the stator winding are cooled by surrounding oil. A drawback with so much oil in the system is the risk of leakage and the extensive cleaning-up process required in the event of a fault condition. The parts of the insulating sheath located outside the slots have a cylindrical part and a conical screening electrode whose task it is to control the electrical field strength in the area where the cable leaves the plate.

It is evident from CCCP 955369 that in another attempt at increasing the rated voltage of a synchronous machine, the oil-cooled stator winding consists of a conductor with insulation for medium-high voltage, having the same dimension for all layers. The conductor is placed in stator slots in the shape of circular, radially situated openings corresponding to the cross-sectional area of the conductor and place required for fixation and cooling. The various radially located layers of the winding are surrounded and fixed in insulating tubes.

Insulating spacer elements fix the tubes in the stator slot. In view of the oil cooling, an inner dielectric ring is also required here to seal the oil coolant from the inner air gap. The construction illustrated has no stepping of the insulation or of the stator slots. The construction shows an extremely narrow, radial waist between the various stator slots, entailing a large slot leakage flow which greatly affects the excitation requirement of the machine.

In a report from the Electric Power Research Institute, EPRI, EL-3391, from April 1984 an exposition is given of the generator concept in which a higher voltage is achieved in an electric generator with the object of connecting such a generator to a power network without intermediate transformers. The report deems such a solution to offer satisfactory gains in efficiency and financial advantages. The main reason that in 1984 it was considered possible to start developing generators for direct connection to the power network was that by that time a superconducting rotor had been developed. The considerable excitation capacity of the superconducting field makes it possible to use air-gap windings with sufficient thickness to withstand the electric stresses.

By combining the construction of an excitation circuit, the most promising concept of the project, together with winding, a so-called "monolith cylinder armature", a concept in which two cylinders of conductors are enclosed in three cylinders of insulation and the whole structure is attached to an iron core without teeth, it was deemed that a rotating electric machine for high voltage could be directly connected to a power network. This solution implied that the main insulation had to be made sufficiently thick to withstand network-to-network and network-to-earth potentials. Besides it requiring a superconducting rotor, an obvious drawback with the proposed solution is that it requires a very thick insulation, thus increasing the size of the machine. The coil ends must be insulated and cooled with oil or freones in order to direct the large electric fields in the ends. The whole machine is to be hermetically enclosed to prevent the liquid dielectric medium from absorbing moisture from the atmosphere.

The present invention is related to the above-mentioned problems associated with avoiding damage to the surface of the cable upon insertion into the stator slots and avoiding wear against the surface caused by vibration during operation. The slot through which the cable is inserted is relatively uneven or rough since in practice

it is extremely difficult to control the position of the laminated plates sufficiently exactly to obtain a perfectly uniform surface. The rough surface has sharp edges which may shave off parts of the semiconductor layer surrounding the cable. This leads to corona and break-through at operating voltage.

5

When the cable is placed in the slot and adequately clamped there is no risk of damage during operation. Adequate clamping implies that forces exerted (primarily radially acting current forces with double mains frequency) do not cause vibrations that cause wear on the semiconductor surface. The outer semiconductor is to thus be protected against mechanical damage even during operation.

10

During operation the cable is also subjected to thermal loading so that the XLPE material expands. The diameter of a 145 kV XLPE cable, for instance, increases by about 1.5 mm at an increase in temperature from 20 to 70°C. Space must therefore be allowed for this thermal expansion.

15

Against this background the object of the present invention is to solve the problems of achieving a machine of the type under consideration so that the cable is not subjected to mechanical damage during operation as a result of vibrations, and which permits thermal expansion of the cable. Achieving this would enable the use of cables that do not have a mechanically protecting outer layer. In such case the outer layer of the cable consists of a thin semiconductor material which is sensitive to mechanical damage.

20

25

According to the invention this has been solved by giving a machine of the type described in the preamble to claim 1 the special features defined in the characterizing part of this claim.

30

In the present application the terms "radial", "tangential" and "axial" direction have the stator as reference unless expressly stated otherwise. The terms "deactivated" and "activated" spring member are also used in the application. By "deactivated spring member" is here implied a spring member that is locked in a certain position so that its spring force is absorbed by the locking member but is otherwise substantially eliminated. By "activated spring member" is implied a

35

spring member that is not locked in this manner and is thus free to exert a spring force.

- 5 Deactivating the spring members as defined in claim 1 when they are arranged in the slots, either before they are inserted into the slots or after they have been inserted, enables them to be restrained so that they do not impede or complicate insertion of the cable into the slots since a clearance is hereby obtained. Once the cable is in place and the spring members are activated they will be able to abut against the cable lead-throughs to support them, hereby eliminating the risk of
- 10 the damages mentioned above caused by vibration. The free clearance during winding of the cables also reduces the risk of damage when winding is being performed. During operation the cable lead-through have room to expand.

- In a preferred embodiment of the method a support body which can be pressed against at least one cable lead through, preferably two cable lead-throughs, is arranged between the spring member and the cable lead-throughs, in which case the spring member is arranged at one of the slot walls. In a modification of this embodiment, spring members and support bodies are arranged at both slot walls. The arrangement of such support bodies in this manner enables the cable to be
- 20 effectively secured with forces operating in radial and tangential direction and the support members can be shaped with support surfaces to fit the cable penetrations in order to achieve optimum distribution of pressure.

- In a preferred alternative of this embodiment, a pressure member is arranged to press one or both support members out towards the relevant slot wall. The necessary free space is hereby created in a simple manner for the cable lead-through.
- 25

- In a particularly preferred embodiment the pressure member serves to deactivate the spring members by compressing them. The spring members can then easily be activated by simply removing the pressure member once the cable is in place.
- 30

It is advantageous to arrange the spring members in the form of a corrugated, preferably laminated plate spring, a "Krempel wave".

- This embodiment enables a practical way of deactivating or activating the spring member by gluing the plate spring to a flat surface so that it is flat and then activating it by releasing the adhesive joint, e.g. by heating. Such an embodiment may in certain cases be an advantageous alternative to using the pressure member mentioned earlier for deactivating and activating the spring member, and in other cases may constitute a complement thereto.

- The embodiment of a glued Krempel wave may also be used to advantage for the radial clamping of the windings, and in that case arranged on a lid fitted to cover the opening of the slot and act in activated state against the radially innermost cable lead-through.

- The above and other advantageous embodiments of the method according to the invention are defined in the sub-claims to claim 1.

- By using corrugated plate springs to clamp the cable lead-throughs as in the machine according to the invention, a simple and expedient arrangement is achieved to eliminate the problems encountered when high-voltage cable is used in the windings, as discussed in the introduction. The machine according to the invention also has the advantage of being suitably manufactured in accordance with the method of the invention.

- Advantageous embodiments of the machine according to the invention are defined in the sub-claims to claim 13. The special advantages as revealed in the account above of various embodiments of the method according to the invention are achieved in these embodiments.

- The invention will be explained in more detail in the following description of preferred embodiments, with reference to the accompanying drawings in which;

- Figure 1 shows schematically an end view of a sector of the stator in a machine according to the invention,

- Figure 2 shows a cross-section through a cable used in the machine according to the invention,

Figure 3 shows a partial section through a stator slot according to a first embodiment of the invention,

5 Figure 4 shows a section corresponding to that in Figure 3, but illustrating a second embodiment of the invention,

Figure 5 shows a section through a stator slot according to a third embodiment of the invention,

10 Figure 6 shows an activated spring member according to a preferred embodiment of the invention,

Figure 7 shows the spring member in Figure 6 deactivated,

15 Figure 8 is a section through a stator slot according to a fourth embodiment of the invention.

In the axial view shown schematically in Figure 1 through a sector of the stator 1 of the machine, its rotor is designated 2. The stator is composed in conventional manner of a laminated core of sheet steel. The figure shows a sector of the machine, corresponding to one pole division. From a yoke part 3 of the core situated radially outermost, a number of teeth 4 extend radially in towards the rotor 2 and are separated by slots 5 in which the stator winding is arranged. The cables 6 in the windings are high-voltage cables which may be of substantially the same type as high-voltage cables used for power distribution, so-called XLPE cables. One difference is that the outer mechanically protective sheath that normally surrounds such a cable has been eliminated. The cable thus comprises only the conductor, an inner semi-conductor layer, an insulating layer and an outer semi-conducting layer. The semi-conductor layer, sensitive to mechanical damage, is thus exposed on the surface of the cable.

20

25

30

In the drawings the cables 6 are illustrated schematically, only the conducting central part of the cable lead-through or coil side being illustrated. As can be seen, each slot 5 has varying cross-section with alternating wide parts 7 and narrow parts 8. The wide parts 7 are substantially circular and surround cable lead-throughs, whereas the waist parts between these form narrow parts 8. The waist

35

parts serve to radially position each cable lead-through. The cross-section of the slot as a whole also becomes slightly narrower in radial direction inwards. This is because the voltage in the cable lead-throughs is lower the closer they are situated to the radially inner part of the stator. Slimmer cable lead-throughs can therefore
5 be used here, whereas increasingly coarser cable lead-throughs are required further out. In the example illustrated cables of three different dimensions are used, arranged in three correspondingly dimensioned sections 9, 19, 11 of the slots 5.

Figure 2 shows a cross-sectional view of a high-voltage cable 6 according to the
10 present invention. The high-voltage cable 6 comprises a number of strand parts 31 made of copper (Cu), for instance, and having circular cross-section. These strand parts 31 are arranged in the middle of the high-voltage cable 6. Around the strand parts 31 is a first semi-conducting layer 32. Around the first semi-conducting layer 32 is an insulating layer 33, e.g. XLPE insulation. Around the insulating layer 33 is a second semi-conducting layer 34. The concept "high-voltage cable"
15 in the present application thus need not include the metal screen and the outer protective sheath that normally surround such a cable for power distribution.

In the embodiment illustrated in Figure 3 the slot 5 has a profile that deviates
20 somewhat from that shown in Figure 1 in that alternate waist parts 8 have greater width. On the one side of alternate waist parts 8 the slot wall has a profile section 12 that follows the tangent between adjacent wide, circular parts 7. The waist parts thus enlarged are arranged alternately where the slot wall profile section 12 formed as a tangent is alternately situated on both slot walls. The purpose of the
25 enlarged parts is to provide room for spring and support member. It will be understood that the enlarged part need not necessarily be formed by the wall section 12 following a tangent. The section 12 may be either outside or inside this tangent plane and need not be situated per se in a radial plane to the stator, or even be flat. Furthermore, the enlarged portions need not be arranged alternately.
30 Instead all of them may be arranged on the same side of the slot.

In the space with substantially triangular cross-section that is formed between the wall section 12 and the two cable parts 6 is a cable support body 14, and between this and the wall section 12 is a spring member 13. The cable support body 14
35 extends axially through the whole slot, thereby forming a rod-like element. The spring member 13, suitably made of a corrugated laminated plate spring

containing glassfibre, extends axially through the whole slot. The spring member 13 may also be arranged at only certain points in axial direction, as may also the support body 14.

- 5 The support body 14 has a support surface in the shape of a cylinder arc facing each cable lead-through 6, its radius fitting the radius of the cable so that a large support surface is obtained. The support body 14 is pressed against the cable lead-throughs by means of the spring member 13 with a force F directed radially relative to the cable lead-throughs 6 so that each cable lead-throughs 6 is clamped
10 between the support body 14 and the opposite wall, along the whole length of the cable lead-through in the example shown.

- To enable insertion of the cable during winding it must be ensured that the support body 14 is not in the way. Figure 3 shows a way of achieving this when the support bodies 14 and spring members 13 are placed in the slots 6 before the cable
15 is wound. A pressure member 15 is inserted between each support body 14 and the wall portion opposite. This may be in the form of a rod extending along the whole slot. The rod has a width in the transverse direction of the slot that is adjusted so that the rod 15 presses the support member 14 against the wall section
20 12 and against the action of the spring member 13. This is thus locked in a deactivated position and the support body 14 is pressed back by the rod 15.

- When the cable has been wound the rods 15 are withdrawn from the slot. Locking of the spring member is thus released so that it is activated and presses the support
25 body 14 against the cable lead-throughs 6.

- Figure 4 illustrates an embodiment based on the same principle as that illustrated in Figure 3, but somewhat modified. Briefly this can be described as a double-acting variant. In this embodiment the opposite slot wall is also formed as a wall section connecting the circular parts 7 so that no waist part is formed. Space is
30 hereby provided for a support body 14a, 14b with spring members 13a, 13b to be arranged on each side of the slot. The pressure member or rod 15a is in this case arranged between the two support bodies 14a, 14b and presses these against respective wall parts 14a, 14b against the action of respective spring members 13a, 13b. In other respects the design is in principle the same as that described in
35

connection with Figure 3 and the measures for deactivating and activating the spring members are equivalent.

Figure 5 illustrates another embodiment which differs from that illustrated in Figure 3 primarily in the method of deactivation and activating the spring member 13c. The spring member 13c is manufactured in the form of a corrugated laminated plate spring which, with the slot wall 12c as support, presses the support body 14c, preferably made of rubber, against the cable lead-throughs 6. A plate 16 is also arranged between the plate spring 13c and the slot wall 12c.

Figures 6 and 7 show the spring member 13c of Figure 5 on an enlarged scale in activated and deactivated state, respectively.

The plate spring 13c, which may consist of triazine resin and glass fabric or polyimide resin and glass fabric, for instance, is in Figure 7 glued to one side of the plate 16, the other side of which abuts the slot wall 12c. The plate 16 may suitably consist of glass fabric/bakelite. The plate spring 13c is thus formed to assume a flat shape and then deactivated. The type of glue is selected so that it melts at the temperature, about 70°C, reached in this area when the machine is in operation. When the glue melts, the plate spring 13c loosens from its forced flat shape and assumes the corrugated shape shown in Figure 6. It has thus been activated for its spring function and presses against the support body 14c in Figure 5.

The plate 16 with the plate spring 13c glued onto it is inserted axially into its place in the slot before the cable is drawn. Since the plate spring 13c is deactivated, the support body 14c is restrained so that it does not impede insertion of the cable.

Figure 8 shows yet another embodiment of the invention. The Figure shows the radially inner end of a slot, whose radially inwardly facing opening is covered by a slot lid 17. A plate spring 13d is arranged on the slot lid 17 in similar manner to that described in connection with Figures 6 and 7. The slot lid 17 with plate spring 13d may be applied after the cables 6 have been wound. The plate spring 13d is then activated either as described or by means of a few light knocks on the outside of the slot lid 17, thereby causing the glue joint to be released. When the plate spring 13d has been activated it will press radially upwards against the inner

cable lead-through and, via that, also against the cable lead-throughs situated further out.

0
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

24 -09- 1998

The Swedish Patent Office
PCT International Application

AMENDED CLAIMS

1. A method of manufacturing the stator for a rotating electric machine, characterized in that a high-voltage cable is drawn through slots in the stator to form the stator windings, the cable having an insulation system comprising at least outer and inner semiconducting layers and solid insulation, and in that spring members are deactivated and arranged in at least one slot, and that said spring members are activated after the cables have been wound.
2. A method as claimed in claim 1, in which a first spring member is arranged to be supported by one of the slot walls, that a first support body is arranged between the spring member and at least one cable lead-through, preferably two cable lead-throughs, said first support body being arranged to be able to be pressed against at least one cable lead-through.
3. A method as claimed in claim 2, wherein a second spring member is arranged to be supported by the opposite slot wall and immediately opposite said first spring member, that a second support body is arranged between said second spring member and said at least one cable lead-through, said second support body being arranged to be able to be pressed against said at least one cable lead-through.
4. A method as claimed in claim 2, wherein a pressure member is arranged between said first support body and the opposite slot wall so that the pressure member, via said first support body, presses against said first spring member.
5. A method as claimed in claim 3, wherein a pressure member is arranged between said first and second support bodies so that the pressure member, via these, presses against said first and second spring members.
6. A method as claimed in claim 4 or claim 5, wherein said pressure members are arranged so that said spring members are

24-09-1998

deactivated and that the spring members are activated by removal of the pressure member.

7. A method as claimed in any of claims 1-6, wherein the spring member comprises a corrugated, preferably laminated, plate spring.

8. A method as claimed in claim 7, wherein said deactivation entails gluing the plate spring to a flat surface so that it acquires a flat shape and that said activation entails releasing the glue joint.

9. A method as claimed in claim 8, dependent on claim 1, wherein the plate spring is glued to the inside of a slot lid fitted at the radially inwardly directed opening of the slot.

10. A method as claimed in claim 8 or claim 9, wherein the glue joint is released by heating, preferably by the transfer of heat generated in the cable.

11. A method as claimed in claim 9, wherein the glue joint is released by knocking against the outside of the lid.

12. A method as claimed in any of claims 1-11, wherein said spring members extend along substantially the entire axial extension of the stator.

13. A rotating electric machine comprising a stator with windings (6) drawn through slots (5) in the stator (1), characterized in that at least one winding (6) is a high-voltage cable with an insulation system comprising at least two semiconducting layers (32, 34), each layer essentially constituting an equipotential surface, and also including solid insulation (33), and in that at least one spring member in the form of a corrugated, preferably laminated plate spring (13c, 13d) is arranged to exert pressure on at least one cable lead-through.

24 -09- 1998

14. A machine as claimed in claim 13, wherein at least one of said layers (32, 34) has substantially the same coefficient of thermal expansion as the solid insulation (33).
- 5 15. A rotating electric machine as claimed in claim 13 or claim 14, wherein said spring member (13c) is arranged between one slot wall (12c) and a support member (14c) which is held pressed by the spring member (13c) against at least one, preferably two cable lead-throughs (6).
- 10 16. A rotating electric machine as claimed in claim 13 or claim 14, wherein said spring member (13d) is arranged between a slot lid (17) fitted on an inwardly directed opening of the slot and the radially innermost cable lead-through (6).
- 15 17. A rotating electric machine as claimed in any of claims 14-16, wherein said spring members (13c, 13d) extend along substantially the whole axial extension of the stator (1).
-

1 / 3

Fig. 1




Fig. 2




Fig. 5




Fig. 4





Fig. 3



3 / 3

Fig. 6




Fig. 7





Fig. 8



Declaration, Power Of Attorney and Petition

Page 1 of 3

WE (I) the undersigned inventor(s), hereby declare(s) that:

My residence, post office address and citizenship are as stated below next to my name,

We (I) believe that we (I am) the original, first, and joint (sole) inventor(s) of the subject matter which is claimed and for which a patent is sought on the invention entitled

ROTATING ELECTRICAL MACHINE COMPRISING HIGH-VOLTAGE STATOR WINDING

AND SPRING-DEVICE SUPPORTING THE WINDING AND METHOD FOR
MANUFACTURING SUCH MACHINE

the specification of which

☐ is attached hereto.

☒ was filed on _____ as

Application Serial No. _____

and amended on _____.

☒ was filed as PCT international application

Number PCT/SE97/00906

on 27 May 1997,

and was amended under PCT Article 19

on _____ (if applicable).

We (I) hereby state that we (I) have reviewed and understand the contents of the above-identified specification, including the claims, as amended by any amendment referred to above.

We (I) acknowledge the duty to disclose information known to be material to the patentability of this application as defined in Section 1.56 of Title 37 Code of Federal Regulations.

We (I) hereby claim foreign priority benefits under 35 U.S.C. § 119(a)-(d) or § 365(b) of any foreign application(s) for patent or inventor's certificate, or § 365(a) of any PCT International application which designated at least one country other than the United States, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate, or PCT International application having a filing date before that of the application on which priority is claimed. Prior Foreign Application(s)

Application No.	Country	Day/Month/Year	Priority Claimed
<u>9602079-7</u>	<u>SWEDEN</u>	<u>29 May 1996</u>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
<u>9604030-8</u>	<u>SWEDEN</u>	<u>04 November 1997</u>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
_____	_____	_____	<input type="checkbox"/> Yes <input type="checkbox"/> No
_____	_____	_____	<input type="checkbox"/> Yes <input type="checkbox"/> No

We (I) hereby claim the benefit under Title 35, United States Code, § 119(e) of any United States provisional application(s) listed below.

_____ (Application Number)	_____ (Filing Date)
_____ (Application Number)	_____ (Filing Date)

We (I) hereby claim the benefit under 35 U.S.C. § 120 of any United States application(s), or § 365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application in the manner provided by the first paragraph of 35 U.S.C. § 112, I acknowledge the duty to disclose information which is material to patentability as defined in 37 CFR § 1.56 which became available between the filing date of the prior application and the national or PCT International filing date of this application.

Application Serial No.	Filing Date	Status (pending, patented, abandoned)
PCT/SE97/00906	27 May 1997	
_____	_____	_____
_____	_____	_____

And we (I) hereby appoint: Norman F. Oblon, Registration Number 24,618; Marvin J. Spivak, Registration Number 24,913; C. Irvin McClelland, Registration Number 21,124; Gregory J. Maier, Registration Number 25,599; Arthur I. Neustadt, Registration Number 24,854; Richard D. Kelly, Registration Number 27,757; James D. Hamilton, Registration Number 28,424; Eckhard H. Kuesters, Registration Number 28,870; Robert T. Pous, Registration Number 29,099; Charles L. Gholz, Registration Number 26,395; Vincent J. Sunderdick, Registration Number 29,004; William E. Beaumont, Registration Number 30,996; Steven B. Kelber, Registration Number 30,073; Robert F. Gnuse, Registration Number 27,295; Jean-Paul Lavalleye, Registration Number 31,451; Stephen G. Baxter, Registration Number 32,884; Martin M. Zoltick, Registration Number 35,745; Robert W. Hahl, Registration Number 33,893; Richard L. Treanor, Registration Number 36,379; Steven P. Weihrouch, Registration Number 32,829; John T. Goolkasian, Registration Number 26,142; Marc R. Labgold, Registration Number 34,651; William J. Healey, Registration Number 36,160; Richard L. Chinn, Registration Number 34,305; Steven E. Lipman, Registration Number 30,011; Carl E. Schlier, Registration Number 34,426; James J. Kulbaski, Registration Number 34,648; Catherine B. Richardson, Registration Number 39,007; Richard A. Neifeld, Registration Number 35,299; J. Derek Mason, Registration Number 35,270; and Surinder Sachar 34,423, our (my) attorneys, with full powers of substitution and revocation, to prosecute this application and to transact all business in the Patent Office connected therewith; and we (I) hereby request that all correspondence regarding this application be sent to the firm of OBLON, SPIVAK, MCCLELLAND, MAIER & NEUSTADT, P.C., whose Post Office Address is: Fourth Floor, 1755 Jefferson Davis Highway, Arlington, Virginia 22202.

We (I) declare that all statements made herein of our (my) own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issuing thereon.

Mats LEIJON
NAME OF FIRST ~~SOLE~~ INVENTOR

Residence: Hyvlargatan 5, S-723 35

Vasteras, SWEDEN ~~SE~~

Mats Leijon
Signature of Inventor

Citizen of: SWEDEN

Post Office Address: same as above

Date 98-11-23

200 Bengt KOTHMAN

NAME OF SECOND JOINT INVENTOR

Bengt Kothman

Signature of Inventor

98-11-13

Date

300 Hans-Olof KALLDIN

NAME OF THIRD JOINT INVENTOR

H O Kalldin

Signature of Inventor

99-01-28

Date

400 Bertil LARSSON

NAME OF FOURTH JOINT INVENTOR

Bertil Larsson

Signature of Inventor

98-11-13

Date

NAME OF FIFTH JOINT INVENTOR

Signature of Inventor

Date

Residence: Profilgatan 16, S-723 36

Vasteras, SWEDEN SEX

Citizen of: SWEDEN

Post Office Address: same as above

Residence: Grenadjargatan 9, S-723 46

Vasteras, SWEDEN SEX

Citizen of: SWEDEN

Post Office Address: same as above

Residence: Sammetsvagen 12, S-724 76

Vasteras, SWEDEN SEX

Citizen of: SWEDEN

Post Office Address: same as above

Residence: _____

Citizen of: _____

Post Office Address: _____